

# Green Valley Landscaping

110 Stephen Court  
Middletown, DE 19709  
Phone (302) 437-4386  
[James.Caccamo@Gmail.com](mailto:James.Caccamo@Gmail.com)

## **PROPOSAL**

**For:**

### **MOT CHARTER HIGH SCHOOL BASEBALL AND SOFTBALL FIELDS**

February 4, 2015

**Green Valley Landscaping, LLC.** Is please to present you with the following proposal, if you have any questions or want to accept the contract, please contact me at 302-437-4386 or [James.Caccamo@Gmail.com](mailto:James.Caccamo@Gmail.com).

#### **Construction Services**

##### **Scope of Work:**

This proposal provides for the construction for the baseball/softball infield, pitching mound, batter box's and sod infield (baseball filed only) and outfields. This type of construction will require earth-disturbing activities and shall adhere to all state and county code requirements.

##### **Period of Coverage:**

This proposal shall be in affect for period of ninety (90) days.

##### **Task Breakdown and Pricing:**

Excavation	- Grade field to a slope of .5 – 1% slope	
Infield Construction Baseball 90ft Bases	- Infield soil/dirt mixture – Premium Mix of 51% Sand, 16% Clay and 33% Silt. 4" thick base. - Build pitching mound and batters box with Pitching Mound/Batters Box Select Mixture. - Build Batters Box will be constructed to a 26' Diameter. - Pitching Mound will be constructed utilizing 1" lifts to a height of 10" above final grade and within an 18" Diameter. - Install baseball bases sleeves.	300 Tons  14 Yards.

	- Provide Kwik-Release Bases - Install Pitchers Mound Rubber -Install infield sod as per diagram - Install outfield sod supporting a fence length of 350' to left and right fields. Sod materials selected will be a durable Bermuda Grass.	3 1 9000 sqft. 50,000 sqft
Infield Construction Softball 60ft Bases	- Infield soil/dirt mixture – Premium Mix of 51% Sand, 16% Clay and 33% Silt. 4" thick base. - Build pitching mound and batters box with Pitching Mound/Batters Box Select Mixture. - Build Batters Box will be constructed to a 25' Diameter. - Pitching Mound will be constructed utilizing 1" lifts to a thickness of 4" and within a 16" Diameter. - Install baseball bases sleeves. - Provide Kwik-Release Bases - Install Pitchers Mound Rubber - Install outfield sod supporting a fence length of 225' to left and right fields. Sod materials selected will be a durable Bermuda Grass.	200 Tons  12 Yards.  3 1 20000 sqft.
Cost for:	- Baseball Field - Softball Field	\$36,096.50 \$24,361.67

**Total Contract Price: \$60448.17**

**Option:** Utilize Kentucky Bluegrass 31 grass seed at a cost of. \$7,213.21. If this option is selected you can deduct \$9,802.91 from the contract price. New total contact price would be \$50,646.26.

**Payment Schedule:**

- 50% deposit
- 25% upon final grade
- Balance upon seed/sod installation.